BRUHATH BANGALORE MAHANAGARA PALIKE,
DASARAHALLI ZONE
Office of the Executive Engineer Dasarahalli Division

Schedule - B

BBMP/2021-22/OW/WORK_INDENT50951

Name of Work: Comprehensive Development works in Ward No.13,Shettyhalli Sub Division

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Sri KEMPARAJU	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	KSRRB 300-2. Earthwork excavation by manual means in Ordenary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (PWD SR 2018-19 P.No: 143, I.No.: 19.1)	Cum	22.98	152.0	Rupees One Hundred Fifty Two Only
2	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications.MORTH -100/ Chapter 1 (PW,P& IWTD SR 2018-19, Pg No 16, Item No. 17.1 & 17	Cum	22.98	82.0	Rupees Eighty Two Only
3	KSRB 4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2(PW,P& IWTD SR 2018-19,Page No-13 Item No-4.2)	Cum	17.24	6084.0	Rupees Six Thousand Eighty Four Only

Signature of the Contractor,

Executive Engineer
Dasarahalli Division

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73

4	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete. - of size 450 x 200 x 400 mm (PWD SR 2018-19 P.No: 27, I.No.: 5.29.1)	No	1712.46	527.0	Rupees Five Hundred Twenty Seven Only
5	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 (PWD SR 2018-19 P.No: 180, I.No.:24.1)	Sqm	385.30	94.0	Rupees Ninety Four Only
6	Providing and fixing Executive bench made out of sadarahally grey stone with hand supporter with three line finishing with arch design, with 100mm slab height 90 X length 150 X width 45cms (data rate)	No	30.00	20111.0	Rupees Twenty Thousand One Hundred Eleven Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73.

Executive Engineer,
Dasarahalli Division